

BRUHAT BANGALORE MAHANAGARA PALIKE**DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

Name of Work: Improvements to roads and drains at between 6th Main & 7th Main cross roads, 1st, 2nd cross Manjunatha Nagara in Ward no 14

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	636.00	86.92	Rupees Eighty six & Ninty Two Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	95.40	5159.02	Rupees Five Thousand One hundred Fifty Nine & Two Paise Only
3	Providing and removing centering , shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications,	Sqm	2120.00	310.58	Rupees Three hundred ten & Fifty Eight Only
4	Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008- i) Upto 5 m height.	Cum	198.75	6965.26	Rupees Six thousand nine hundred Sixty Five & Twenty Six Only
5	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications	Tonne	15.77	66482.14	Rupees Sixty Six thousand four hundred Eighty two & Fourteen Only

EXECUTIVE ENGINEER-4
Signature of the Contractor
BENGALURU-560 010

Executive Engineer

6	Supplying and fixing precast reinforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	477.00	1698.00	Rupees One thousand Six hundred Ninty Eight Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	636.00	85.65	Rupees Eighty Five & Sixty Five paise Only


EXECUTIVE ENGINEER-4
 KRISHNA RAILWAY DIVISION
 BENGALURU-560 010


 Executive Engineer